



Hambridge Village Hall Fire Alarm Test

To test the Fire Alarm System, follow the instructions below:

1. Turn key or enter code 2143 (amber access light will illuminate)
2. Test call point with test key, Fire alarm system will sound.
3. To silence the sounders. Press silence the internal sounder button and the silence/resound button as displayed on the panel.
4. Make sure the call point is reset.
5. Reset fire alarm system (Control panel reset)
6. System will then reset.
7. Turn key back to normal position or if the code has been used press the exit access mode button.
8. The access light will go out, leaving green supply light present.